

### Sebert Trillingstechniek B.V.

Report M13.001-P13.001 rev.01 Date 26 august 2013



# Vibration tests on a TNAML Luminaire



### ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





Client Technor Benelux B.V. Veersteeg 15 4212 LR Spijk The Netherlands

#### **Contact Person**

Mr. J. Geluk

#### Order conformation

Technor Benelux B.V. Purchase Order Number T13.2.0307

#### Present at the tests

Mr. E. Geluk of Technor Benelux B.V.

**S2T Quotation** E-mail 02 July 2013

Author / Tester

Mr. K. Smits

#### No of pages

13

Revision of report	Date	Changes
M13.001-P13.001	23 August 2013	Content changed

Report M13.001-P13.001 rev.01

Page 2/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





#### **Table of contents**

1.	Intro	oduction	4
2.	Tes	t procedure and equipment	4
	2.1.	General	4
	2.2.	Vibration requirements	5
	2.3	Mounting and orientation of the test items	5
	2.4.	Description of the used apparatus and instrumentation	5
	2.5.	Sketch of the test configuration	6
	2.6.	Measurement uncertainty and tolerances	6
3.	Vibr	ation and shock tests	7
	3.1.	General	7
	3.1.	1. Test A: Vibration test setup	7
	3.2.	Test A: Vibration test result	8
	3.3.	Laboratory ambient (during test)	8
4.	Cor	clusion and remarks	9
	Figure	95	10
	Abbre	viations	12
	Distrik	pution	13

Report M13.001-P13.001 rev.01

Page 3/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



#### 1. Introduction

Under contract of Technor Benelux B.V. at Spijk in The Netherlands, vibration tests have been carried out on a TNAML Luminaire. The vibration test was carried out on 21 August 2013. All dynamic tests have been carried out under ISO 17025 accreditation. Technor Benelux B.V. will carry out the final inspection after the complete test sequence. Purpose of this test is to determine if the test item meets the vibration requirements. In accordance with Technor Benelux B.V. an acceptation criteria was defined. No (pre)conditioning was carried out. The test results in this report will be related to the tested test item only.

#### 2. Test procedure and equipment

#### 2.1. General

One test item has been used for the vibration tests, see Table 1 for the details of the test item. During the test the test item was not operational. The test item which arrived on 15 August 2013 was checked before starting the test and no deviations were found.

Type designation	Lighting luminaire
Product number	TNAML 2x36 E
Serial number	T13.00255
Weight	+/- 15 kg
Figure	#1

|--|

Report M13.001-P13.001 rev.01

Page 4/13

Date 26 August 2013

### ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



### 2.2. Vibration requirements

The following table (Test A) present the test specifications. See Table 2 for the test plan.

Normative document	IEC 60068-2-6:2008 Environmental testing - Part 2-6 Tests – Test Fc: Vibration (sinusoidal)
Test standard	IEC 60068-3-3:1991
Sine vibration profile	4,9 to 50,1Hz 0,75g acceleration (vertical) 4,9 to 50,1Hz 1,5g acceleration (horizontal)
Sweep rate	1 oct/min
Sweep cycles	2 sweeps (1 up and 1 down per direction)
Direction	in three mutually perpendicular directions
Operational during test	No, after the test the functionality needs to be tested

#### Test A: Sine vibration test specifications

#### Table 2: Test plan

Step	Test	Direction
1	А	Vertical (Z)
2	А	Horizontal longitudinal (Y)
3	A	Horizontal transversal (X)

#### 2.3 Mounting and orientation of the test items

The test item was mounted on the vibration table through its normal points of attachment and in normal orientation with respect to the vertical. The test were carried out in three mutually perpendicular directions, see Figure #2 for de vertical (Z) direction, see Figure #3 for the horizontal longitudinal (Y) direction and see Figure #4 for the horizontal transversal (X) direction.

#### 2.4. Description of the used apparatus and instrumentation

Apparatus and/or instrumentation	atus and/or Supplier Model Number		Serial Number	Last / N Calibration and/or	lext date of n, Verification Inspection
Electric-dynamic shaker	Tira	TV 59355/AIT- 440 TGT Model 48XXL	036/07	25-10-12	25-10-13
ICP Accelerometer (check/cross axis point)	PCB Piezotronics	356B21	90931XYZ	05-09-12	05-09-13
ICP Accelerometer (reference point)	PCB Piezotronics	353B34	106991	24-01-13	24-01-14
Shaker control system	Dactron	Laser	4637789	08-11-12	08-11-13
Signal Conditioner	PCB Piezotronics	482C16	428	30-05-13	30-05-14

Report M13.001-P13.001 rev.01

Page 5/13

Date 26 August 2013

### ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



Monitoring of the environmental conditions	Novasina	ClimaLog 30	1206059	20-11-12	20-11-14
--	----------	-------------	---------	----------	----------

#### 2.5. Sketch of the test configuration



#### 2.6. Measurement uncertainty and tolerances

All the measurements were carried out with a signal tolerance includes instrumentation errors lower than 5% according to the standards. The combined standard uncertainly (k=2) and the expanded uncertainty (k=2) is lower than 10%. For lower vibration frequency (>1 <10Hz), large size and high mass the signal tolerance is lower than 10%. Temperature and relative humidity are not operational factors.

Report M13.001-P13.001 rev.01

Page 6/13

Date 26 August 2013

### ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



#### 3. Vibration and shock tests

#### 3.1. General

The sine sweep vibration tests were carried out in three mutually perpendicular directions on a shaker.

#### 3.1.1. Test A: Vibration test setup

The vibration acceleration tolerance at the reference point is  $\leq 1$ dB and the check point  $\leq 2$ dB. The maximum vibration amplitude at the check points in any axis perpendicular to the specified axis does not exceed 50% of the specified amplitude up to 500 Hz (as described in IEC 60068-2-6:2008 paragraph 4.1.2.1). See Table 3 for the used vibration parameters.

System	Parameters
Controller	Closed loop – Automatic Equalization
Max. Test Frequency:	150.00 Hz
Sweep Type:	Logarithmic
Sweep Rate:	1.000000 Oct/Min
Measurement Strategy:	Single Channel
Filter Type:	Proportional
Band Width:	25%
Drive Limit:	10.00 Volts
Abort Latency:	0.30 seconds
Compression Speed Type:	Adaptive
Compression Speed:	Fast

Table 3: Vibration control parameters

#### 3.1.2 Accelerometers location and orientation

See Table 4 for the location and orientation of the used accelerometers during the tests.

	Table 4:	Used	acce	lerom	eters
--	----------	------	------	-------	-------

Test item	Direction	Input channel	Accelerometer Serial number	Location	Figure
#1	X, Y, Z	1	106991	On the vibration table	-
#1	X, Y, Z	2,3,4	90931 (XYZ)	On the vibration table	-

Report M13.001-P13.001 rev.01

Page 7/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





#### 3.2. Test A: Vibration test result

A vibration test in the three mutually perpendicular directions has been carried out, see Table 5 for the summary. See Figure #5 for a typical vibration plot. During the vibration test in Y direction 2 connection bolts came loose see Figure #6, in accordance with Technor Benelux B.V. the bolts have been tightened and further testing continued. No visual damage or functional errors have been found on the test item after the complete test sequence.

Test item	Direction	Test time [min]	Remarks
#1	Vertical (Z)	7	Pass
#1	Horizontal longitudinal (Y)	7	Pass, connection bolts came loose.
#1	Horizontal transversal (X)	7	Pass

#### Table 5: Vibration test result summary

#### 3.3. Laboratory ambient (during test)

See Figure #7 for the environmental measurements during the test sequence.

Report M13.001-P13.001 rev.01

Page 8/13

Date 26 August 2013

### ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





#### 4. Conclusion and remarks

One test item has been subjected to vibration tests according to the normative document: IEC 60068-2-6:2008 Environmental testing - Part 2-6 Tests – Test Fc: Vibration.

See the following table for the summary of the test results:

Test A: Vibration test	During the vibration test in Y direction 2 connection bolts came loose, in accordance with Technor Benelux B.V. the bolts have been tightened and further testing continued. No visual damage or
	functional errors have been found on the test item after the complete test sequence.

Technor Benelux B.V. carried out the final inspection on the test item after the completed test sequence, the TL and LED lighting were still functional.

Approved by M.J.H. Magendans

Director / Test Specialist Mechanical Simulations

Test is carried out by K. Smits Test Engineer Mechanical Simulations

Report M13.001-P13.001 rev.01

Page 9/13

Date 26 August 2013

## ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



Figures

Figure 1: Test item



Figure 2: Test setup Z direction



Figure 3: Test setup Y direction



Figure 4: Test setup X direction



Figure 5: Test A vibration plot



Figure 6: Test A test result



Report M13.001-P13.001 rev.01

Page 10/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





#### Figure 7: Environmental measurement



Report M13.001-P13.001 rev.01

Page 11/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands



#### Abbreviations

Acc	Acceleration
ASD	Acceleration Spectral Density
AvC	Average Control
dB	decibel, sound level
DOF	Degrees of Freedom
Drive	Voltage output of the controller used to drive the shaker
DUT	Device under test
Dwell	Endurance test on 'fixed' frequency
Fn	Natural frequency
g	Acceleration due to gravity (equal to 9,81 m/s <sup>2</sup> )
Hz	Hertz
kg	Kilogram
Manuf	Manufacturer
ms	Milliseconds, nominal duration
Ν	Newton (force)
Oct/min.	Sweep rate
Oper	Operational
OS	Operational Shock
Ра	Pressure
PK	Peak
PK-PK	Peak to Peak
PSD	Power Spectral Density
Q	Quality, Sharpness measure of a resonance
Res	Resonance
RS	Resonance Survey
RMS	Root Mean Square
Seq	Sequence
S/N	Serial Number
SRS	Shock Response Spectrum
Sweep	One sweep up or down
Sweep cycle	One sweep up and down
TS	Test Sequence
V	Voltage

Report M13.001-P13.001 rev.01

Page 12/13

Date 26 August 2013

# ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands





#### Distribution

Report	M13.001-P13.001 rev.01
Title	Vibration tests on a TNAML Luminaire
Institute	Sebert Trillingstechniek B.V at Bergschenhoek in The Netherlands

Company:	Number of copies
<u>Technor Benelux B.V.</u> Mr. E. Geluk	1
<u>Sebert Trillingstechniek B.V.</u> Mr. M.J.H. Magendans	1

All rights reserved. No part of this report may be reproduced in any form by print, photo print, microfilm or any other means without the previous written permission from Sebert Trillingstechniek B.V. All information which is classified according to Dutch regulations shall be treated by the recipient in the same way as classified information corresponding value in his own country. No part of this information will be disclosed to any third party.

Report M13.001-P13.001 rev.01

Page 13/13

Date 26 August 2013

## ISO/IEC 17025 Accredited and ISTA® Certified Testing Laboratory

Sebert Trillingstechniek B.V. Weg en land 18 2661 DB Bergschenhoek The Netherlands

